BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34119

APPROVED SCHEDULE - B

BTP/PSMP/E-PMT/19/2018-19, Date: 06.02.2019

onstruction of Drain from Gangamma Temple Road to Chikkasiddappa Layout Amruthahalli in ward no 07 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARAYANAPPA VENKATA REDDY ( )		
				In Figures		In Words
1	107.9	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications.MORTH / Chapter 3(I No-19.1, P No-143)	Cum	252.49	27243.67	Rupees Two Hundred Fifty Two and Forty Nine Paise Only
2	74.7	KSRB2.8:ProvidingandFillinginfoundationwithgranite/trapbrokenmetal100mm.anddownsize,withapprovedsandincludinghandpacking,ramming,watering,includingcostofallmaterialsandlabourwithallleadandlift.completeasperspecifications.specification.No.KBS(P.No.7, I.No.2.15 of PW,P&IWTD S.R 2016-17)	Cum	2574.74	192333.08	Rupees Two Thousand Five Hundred Seventy Four and Seventy Four Paise Only
3	24.9	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3 of PWD SR 2018-19)	Cum	5408.12	134662.19	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
4	99.6	KSRB 4 6.1:Providing and removingc entering, shuttering,strutting, proppingetc., and removal off or mwork for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specifcation No.KBS4.6.2(P.No.16,I.No.4.28 of PW, P&IWTD SR 2016-17)	Sqm	273.48	27238.61	Rupees Two Hundred Seventy Three and Forty Eight Paise Only
5	498	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2(I No-4.31,P No-16)	Sqm	379.48	188981.04	Rupees Three Hundred Seventy Nine and Forty Eight Paise Only
6	99.6	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification. Specification No. KBS 4.6.2(P.No.15, I.No.4.30 of PW,P&IWTD SR 2016-17)	Sqm	466.4	46453.44	Rupees Four Hundred Sixty Six and Forty Paise Only
7	169.32	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) P.No.18, I.No.4.48of PW,P&IWTD SR 2018-19)	Cum	4589.0	777009.48	Rupees Four Thousand Five Hundred Eighty Nine Only

Signature of the contractor

13/06

Executive Engineer

13/06

		Description	Unit	Approved Tender Rates of NARAYANAPPA VENKATA REDDY ( )		
				In Figures		In Words
8	14.39	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3(I No-4.46.2,P No-18)	Tonne	61325.0	882466.75	Rupees Sixty One Thousand Three Hundred Twenty Five Only
					2276388.26	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

13/06

13/06